


15-039-19025-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Decatur County, Sec. 22 Twp. 2S Rge. 28 ~~EX~~ (W)

Location as "NE/CNW/SW" or footage from lines C NE SE

Lease Owner Rains & Williamson Oil Co.

Lease Name RUZICKA Well No. 1

Office Address 412 Union Center, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed June 8 1962

Application for plugging filed June 8 1962

Application for plugging approved June 8 1962

Plugging commenced June 8 1962

Plugging completed June 8 1962

Reason for abandonment of well or producing formation no oil or gas found in commercial quantities

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3710 feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	160'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set plug at 550' and cement through drill pipe with 20 sacks cement. Fill hole up to bottom of surface with rotary mud. Set plug at bottom of surface (160') and cement through drill pipe with 15 sacks. Fill hole up to 40' of base of cellar. Set plug no. 3 and cap with 8 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 14 1962

CONSERVATION DIVISION  
Wichita, Kansas

6-14-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.  
Address 412 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Wilson Rains (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains  
Wilson Rains - Partner  
412 Union Center, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of June, 19 62

My commission expires JANET JOHNSON  
My commission expires Jan. 25, 1965

Janet Johnson  
Janet Johnson Notary Public.



ROTARY DRILLING LOG

15-039-19025-00-00

Operator: Rains & Williamson, Wilcox Oil Co., Murfin Drilling,  
George Donnelly, Jr.  
NO. 1 RUZICKA, C NE SE, Sec. 22-2S-28W, Decatur County, Kansas

CONTRACTOR: Rains & Williamson Oil Co.      REMARKS:  
COMMENCED: 6/1/62      set 8 5/8" at 160' with 135 sacks,  
COMPLETED: 6/8/62      3% cc

FORMATIONS:

Surface soil and clay	30'
Sand	45'
Shale	160'
Plug and Cement	160'
Shale	935'
Shale & Shells	1575'
Shale & Sand	1652'
Shale & Lime shells	2059'
Shale & Lime	2200'
Shale & Lime	2580'
Lime	2900'
Lime & Shale	3050'
Lime & Shale	3175'
Lime & Shale	3325'
Lime & Shale	3445'
Shale & Lime	3505'
Lime	3538'
Lime	3575'
Lime	3635'
Lime	3710'
Rotary Total Depth	3710'

RECEIVED  
STATE CORPORATION COMMISSION

JUN 18 1962

CONSERVATION DIVISION  
Wichita, Kansas

6-18-62

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

By: *Wilson Rains*  
Wilson Rains - Partner

STATE OF KANSAS      )  
COUNTY OF SEDGWICK )

Before me, the undersigned, a notary Public, within and for said County and State on this 13th day of June, 1962, personally appeared Wilson Rains to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

JANET JOHNSON  
My commission expires Jan. 25, 1965

*Janet Johnson*  
\_\_\_\_\_  
Janet Johnson