

15-039-00111-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
800 BITTING BUILDING  
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM  
File One Copy

Lease Owner Wood River Oil & Refg. Co. Address 321 West Douglas, Wichita, Kans.  
(Applicant)

Lease (Farm Name) Allen well No. 1

Well Location NW NW NE Sec. 34 Twp. 2 Rge. 28 (E)-(W)

County Decatur Field Name (if any) None

Total Depth 3841 Oil    Gas    Dry Hole X

was well log filed with application?    If not, explain: yes.

Date and hour plugging is desired to begin Dec. 20, 1955 8 AM

Plugging of the well will be done in accordance with the Rules and Regulations  
of the State Corporation Commission.

Name of the person on the lease in charge of well for owner Carl Robison

Address 1620 Jefferson, Great Bend, Kans.

Plugging Contractor Heathman-Selligson Drilling Co., Wichita, Kans.

Plugging Contractor's License No. Rotary Drilling Contractor.

Address \_\_\_\_\_

Invoice covering assessment for plugging this well should be sent to \_\_\_\_\_

Wood River Oil & Refg. Co., Address 321 West Douglas, Wichita, Kans.

and payment will be guaranteed by applicant.

REC  
STATE COR

DEC 20 1955

CONSERVATION  
WICHITA

12-28-55

WOOD RIVER OIL & REFINING CO., INC.,

BY [Signature]  
Applicant or Acting Agent

Date Dec. 19, 1955.

PLUGGING  
FILE SEC 34 T 2 R 28W  
BOOK PAGE 26 LINE 2

15-039-00111-00-00

1329

DRILLERS' LOG

NAME: ALLEN #1 DATE SPUDDED: 12-12-55  
 LOCATION: NW/4 NW/4 NE/4 Sec. 34-2S-28W ROTARY COMPLETED: 12-20-55  
 Decatur County, Kansas  
 OPERATOR: Wood River Oil & Refining Co. ELEVATION: 2635 KB  
 2632 DF  
 2630 GR  
 CONTRACTOR: Heathman-Seeligson Drilling Co. ROTARY TOTAL DEPTH: 3841'  
 SURFACE CASING: 7 jts. 8-5/8" 8V new casing cemented at 220.61' w/150 sacks of sack cement and 2 Calcium Chloride. Cement Circulated.  
 OIL STRING: None run - Dry and abandoned 12-20-55

DRILL STEM TESTS

DST #1, 3592-3610, open 1 hr. rec. 75' very salty oil cut mud & 90' salt water. BHP-180#.  
 DST #2, 3666-3690, open 1 hr. rec. 40' mud. BHP-0#.

GEOLOGICAL TOPS (KB)

Anhydrite 2343 (4292)

LOG

(Figures indicate bottom of formation)

Sand & Shale 0 - 160  
 Shale 830  
 Sand & Shale 1000  
 Shale & Shells 1650  
 Sand 1740  
 Shale & Shells 2065  
 Anhydrite - Blaine 2105  
 Shale & Shells 2343  
 Anhydrite 2385  
 Lime & Shale 2525  
 Shale, Shells & Red Bed 2835  
 Shale & Red Bed 2900  
 Shale & Lime 3490  
 Lime 3841

The undersigned, R. J. Loeffler, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

HEATHMAN-SEELIGSON DRILLING CO.

By: *R. J. Loeffler*

Subscribed and sworn to before me, the 22nd day of December, 1955

*D. Marjorie Malt*  
 Notary Public

My commission expires: June 28, 1956.

FILED  
COMMISSION

12-28-55

COMMISSION

PLUGGING  
 FILE SEC 34 T. 2 S. R. 28W  
 BOOK PAGE 26 LINE 2



15-039-00111-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
211 NORTH BROADWAY  
WICHITA, KANSAS

December 22, 1955

Well No. 1  
Lease Allen  
Description NW NW NE Sec. 34-2-28W  
County Decatur  
File No. 26-2

Wood River Oil & Refining Co.,  
321 West Douglas  
Wichita, Kansas

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Eldon Petty, Box 326, Hays, Kansas.

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION

By

A handwritten signature in cursive script that reads "S. S. Greider".

S. S. Greider

WELL PLUGGING SUPERVISOR

cc:  
District Plugging Supervisor