

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

4-6-77

API Number 15 - 039 - 20367 - 00 - 00 (of this well)
Lease Owner Bolyard Oil & Gas, Ltd.
Address Brooks Towers - Suite 20C, 1020 15th Street, Denver, CO 80202
Lease (Farm Name) VOTAPKA Well No. 1
Well Location C NE NE Sec. 30 Twp. 2S Rge. ~~E~~ 28W (W)
County Decatur Total Depth 3875' Field Name _____
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 5:00 p.m. 3-20-77

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:
Bill Craig Address 702 S. 2nd St., Hill City, Ks.

Plugging Contractor Abercrombie Drilling, Inc. License No. _____
Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:
Name Bolyard Oil & Gas, Ltd.
Address Brooks Towers - Suite 20C, 1020 15th St., Denver, Colorado 80202

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge
Applicant or Acting Agent
Jack L. Partridge, Asst. Sec.-Treas.
Date: March 29, 1977

15-039-20367-00-00

CONTRACTOR'S WELL LOG

OPERATOR: Bolyard Oil & Gas, Ltd.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: VOTAPKA #1
 LOCATION: C NE NE, Section 30-2S-28W
 Decatur County, Kansas
 SPUD DATE: 3-08-77
 COMPLETION DATE: 3-20-77

0	315	Surface soil, Sand & Shale
315	2085	Shale
2085	2150	Sand
2150	2348	Shale
2348	2380	Anhydrite
2380	2920	Shale
2920	3295	Lime & Shale
3295	3400	Lime
3400	3635	Lime & Shale
3635	3700	Lime
3700	3738	Lime & Shale
3738	3875	Lime
	3875	Rotary Total Depth

Spud hole at 5:30 p.m. 3-08-77. Drilled 315' of 12 1/4" hole. Ran 8 jts of 8 5/8" surface casing. (Tally 303.26') Set at 313.26' G.L. Cemented with 225 Sx. of Sunset Cement, 3% gel, 2% Ca. Cl., 1 1/2% Ammonia. Cement did circulate. Plug was down at 1:45 a.m. 3-09-77.

T.D. 3875', Set 1st plug at 1300' with 70 sx., 2nd plug at 300' with 20 sx., 3rd plug at 40' with 10 sx. Plug was down at 5:00 p.m. 3-20-77. State Plugger - Gilbert Balthazor.

SAMPLE TOPS:

Anhydrite 2348' (+306)
 B/Anhydrite 2380' (+274)

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

4-6-77

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the VOTAPKA #1 C NE NE, Section 30-2S-28W, Decatur County, Kansas

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 29th day of March, 1977.

Kathy S. Goertz
 Kathy S. Goertz, Notary Public



State of Kansas



15-039-20367-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

March 22, 1977

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Votapka
Description	C NE NE Sec. 30-2-28W
County	Decatur
Total Depth	3875
Plugging Contractor	Abercrombie Drilling, Inc.


Bolyard Oil & Gas, Ltd.
1020 15th Street, Suite 20-C
Denver, Colorado 80202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Gilbert Balthazor, P.O. Box 9, Route #1, Palco, Kansas 67657
is hereby assigned to supervise the plugging of the above
named well.