

6-7

4-041681

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 S. MARKET, ROOM #2078
WICHITA, KANSAS 67202

API number: 15-147-20,480-00-00

NW NE SE /4 SEC. 23, 02 S, 19 W
2475 feet from S section line
940 feet from E section line

Operator license# 5134

Lease Kelly well # 4

Operator: Graham-Michaelis Corporation County Phillips

Address: P.O. Box 247
Wichita, Kansas 67202

Well total depth 3630 ^{117.98} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 303 feet
w/190sxs.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 10:00A.M. Day: 7 Month: June Year: 95

Plugging proposal received from: Leon Kuhn

Company: Graham-Michaelis Corporation Phone:

Were: 5 1/2" casing set @ 3729' w/175 sxs. cement. Perf. at 3340' - 3500'. Anhy. at 1730+ - W.L.M. 3400' - T.O.F. at 2000'
Order 200 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 200# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:30P.M., Day: 7, Month: June, Year: 95

Actual plugging report: Hooked-up to 8 5/8" and pressured up to 500#. Hooked-up to 5 1/2" casing - pumped down 25 sxs. cement with 200# hulls, followed with 11 sxs. gel, followed with 150+ sxs. cement.
Max. P.S.I. 200#. S.I.P. 100#

STATE CORPORATION COMMISSION
JUN 16 1995
06-16-1995
WICHITA, KANSAS

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did[X] / did not[] observe the plugging.

Dennis L. Hamel
(agent)

INVOICED

DATE 6-22-95

INV. NO. 42974