

KANSAS

FORM CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Breck
Administrator
245 North Water
Wichita, Ks. 67202

15-147-00956-00-00

API Number 15 - - - N.A. (of this well)

Operator's Full Name SIERRA PETROLEUM COMPANY, INC.

Complete Address P.O. BOX 247 - WICHITA, KANS. 67201

Lease Name HOPPER ESTATE Well No. # 2

Location SE/4 - NW/4 - NE/4 Sec. 23 Twp. 2^S Rge. 19 (E) (W) W

County PHILLIPS Total Depth 3545 FT

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated _____

Plugging Contractor HELSO CASING PULLING

8-14-80

Address BOX 176 CHASE, KANS. 67524 License No. 683

Operation Completed: Hour 4:45 PM Day 12th Month AUG. Year 1980

The Above well was plugged as follows:

8 5/8" APPROX 200 FT NO RECORD. - 4 1/2" SET AT 3524 FT
PERF'S TOP 3528 FT - PLUG BACK. 3528 FT
BOTTOM PLUGGED - COULDN'T GET DOWN. PIPE PARTED AT 1239 FT
RECOVERED 1239 FT OF 4 1/2"
ORDERED 140 ST 50/50 PERMIX 6% GEL - 18 ST GEL. 6 ST HULL'S - 8 5/8" PLUG.
PUMPED IN WITH PUMP TRUCK.
PUT IN - 3 ST HULL'S - 8 ST GEL - 70 ST CMT - 10 ST GEL - 3 ST HULL'S
AND 70 ST CMT. - MAX PRESSURE 200 LBS CEMENTED BY ALLIED CMT.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Martin Schmidt
Well Plugging Supervisor

DATE 8-14-80

INV. NO. 2866-W

RECEIVED
STATE CORPORATION COMMISSION
AUG 14 1980
CONSERVATION DIVISION
Wichita, Kansas