

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
07-05-1973
JUL 5 1973
CONSERVATION DIVISION
Wichita, Kansas

15-147-000841-00-02

Operator's Full Name Sierra Petroleum Co., Inc.

Complete Address P. O. Box 232 Russell, Kansas 67665

Lease Name Heffrom Unit-Kelly Well No. 2

Location NE NW SE Sec. 23 Twp. 2 Rge. (E) (W) 19

County Phillips Total Depth 3568'

Abandoned Oil Well Gas Well Input Well XX SWD Well D & A

Other well as hereafter indicated Oil well converted to Input well.

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 4:30 P Day 3 Month 7 Year 1973

The above well was plugged as follows:

- Total Depth 3568' 8 5/8 csg set at 160' cwa 80 sk.
- 5 1/2 csg set at 3546' cw 100 sk cmt.
- 5 1/2 csg PBTD 3480' with perf. (3294-3462) No pipe recovered.
- Pumped down annulus (8 5/8-5 1/2) with 40 sk cmt. PP 200 lbs.
- Pumped down 5 1/2 csg with 15 sk gel & water W/500 lbs hulls--50 sk cmt--15 sk gel & water--released 5 1/2 plug and pumped 50 sk cmt by Allied Cementing Co. PP 700 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 7/6/73
INV. NO. 7593-W