

RECEIVED
STATE CORPORATION COMMISSION
07-05-1973
JUL 5 1973

KANSAS

Form CP-3
Rev. 6-4-68

CONSERVATION DIVISION
Wichita, Kansas

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-147-00839-00-01

Operator's Full Name Sierra Petroleum Co., Inc.
Complete Address P. O. Box 232 Russell, Kansas 67665
Lease Name Heffron Unit Well No. 2
Location NW SE NE Sec. 23 Twp. 2 Rge. (E) (W) 19
County Phillips Total Depth 3540*
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated Oil well converted to Input
Plugging Contractor Co. Tools
Address _____ License No. _____
Operation Completed: Hour 10:45 A Day 3 Month 7 Year 1973

The above well was plugged as follows:

Total Depth 3540* 8 5/8 csg set at 228* cwc: 150 sk.
5 1/2 csg set at 3540* cw 160 sk cmt.
5 1/2 csg PBTB 3505 with perf. (3296-3490) No pipe recovered.
Pumped down annulus (8 5/8-5 1/2) with 40 sk cmt. 150 lbs pres.
Pumped down 5 1/2 csg with 15 sk gel & water W/500 lbs hulls--50 sk cmt--15 sk gel &
Water--released 5 1/2 plug and pumped 50 sk cmt by Allied Cementing Co. PP 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Masaryk
Well Plugging Supervisor

DATE 7/6/73
INV. NO. 7594-11