

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-19027-00-00

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 1965
6-1-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Union Texas Petroleum Corporation,

Complete Address: Drawer "D", Great Bend, Kansas.

Lease Name Rehm Well No. 1

Location NE-NE-NW Sec. 33 Twp. 2 Rge. (E) (W) 28

County Decatur Total Depth 3730

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Santa Fe Pipe and Supply, Incorporated,

Address: Box #562, Great Bend, Kansas. License No. 574

Operation Completed: Hour 6:00PM Day 27 Month 5 Year 1965

The Above well was plugged as follows:

197'--3 5/8" Surface pipe, cement circulated with 175 Sx.
3723'--4 1/2" Production casing cemented with 135 Sx. Top perforations @ 3547'.

Sanded well back to 3530' and set 3 sacks cement with dump bailer. Pulled
4 1/2" to 600' and circulated heavy gel mud. (Used 40 Bbl rotary mud plus
10 sacks fresh gel). Pulled 4 1/2" to 540' and displaced 20 Sx. cement thru
4 1/2". Pulled 4 1/2" to 210' and displaced 20 Sx. cement thru 4 1/2". Pulled 4 1/2",
set rock bridge @ 35' and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Zichal
Well Plugging Supervisor

DATE 6/2/65

INV. NO. 1243-W