

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 22 1963
3-22-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-039-19021-00-00

Operator's Full Name Pack Oil Co. Inc.,

Complete Address: 550 4th National Building, Wichita, Kansas.

Lease Name Deines Well No. 1

Location NW-NW-NE Sec. 33 Twp. 2 Rge. (E) (W) 28

County Decatur Total Depth 3755

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Barnes & Sons Pipe Pulling Co.,

Address: 1450 Maple, Russell, Kansas License No. 9

Operation Completed: Hour 5:30P Day 2 Month 3 Year 1963

The Above well was plugged as follows:

242' 8 5/8" surface pipe cement circulated. 3670' 4 1/2", top of perforations @3526'.

Sanded well back to 35 10' and set 5 Sx cement with dump bailer.

Pulled 4 1/2" to 550', circulated heavy gel mud(26 Sx.) and displaced 20 Sx.

cement thru casing. Pulled 4 1/2" to 240' and displaced 20 Sx cement thru

4 1/2". Pulled 4 1/2", set rock bridge @ 35' and 10 Sx. cement to bottom of

cellar. (Recovered 1600' 4 1/2" casing).

I hereby certify that the above well was plugged as herein stated.

DATE 3/14/63

INV. NO. 6919-W

Signed: W. L. Nichols
Well Plugging Supervisor