

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

4-13-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-039-20151-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
APR 13 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas .

Lease Name Jorn Well No. A-2

Location CSW-SW Sec. 28 Twp. 2 Rge. (E) (W) 28

County Decatur Total Depth 3642'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Slawson Drilling Company, Incorporated,

Address 408 One-Twenty Bldg., Wichita, Ks License No.       

Operation Completed: Hour 8:30 PM Day 5 Month 4 Year 1970

The above well was plugged as follows:

256'--8 5/8" Surface casing, cement circulated with 240 Sx.  
Top of Dakota section @ 1150'.

Circulated hole with heavy mud. Pulled DP to 1375' and displaced 100 Sx. cement thru  
DP from 1375' to 1050'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from  
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement from  
bridge to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: A. S. Nichols  
Well Plugging Supervisor

INVOICED

DATE 4/13/70  
INV. NO. 1702-W