

KANSAS

*AP*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-00546-00-00

RECEIVED  
STATE CORPORATION COMMISSION

AUG 11 1971

CONSERVATION DIVISION  
Wichita, Kansas

8-11-71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Donald C. Slawson

Complete Address 408 One Twenty Bldg., Wichita, Kansas 67202

Lease Name Beck Well No. 1

Location NE SE SE Sec. 28 Twp. 2 Rge. (E) (W) 28

County Decatur Total Depth 3775'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Russ Casing Pulling, Inc.

Address Box 1082 Great Bend, Kansas License No. 623

Operation Completed: Hour 3:30 P Day 9 Month 8 Year 1971

The above well was plugged as follows:

~~280~~ Total Depth 3775' 8 5/8 csg set at 182' cwc 150 sk.

5 1/2 csg set at 3775' cw 100 sk cmt.

5 1/2 csg perf. (3674')

Filled 5 1/2 csg W/sd (3650-3775) Dumped 5 sk cmt W/dump bailer. (3615-3650)

Cutoff and recovered 1615' of 5 1/2 csg.

Pumped down 8 5/8 csg W/13 sk gel & water W/5 sk hulls (1780-1060) 70 sk cmt 1060-

780) 12 sk gel & water (780-300) 15 sk cmt (300-240) 5 sk gel & water (240-40)

10 sk cmt. (40-0)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/12/71

INV. NO. 4135-W

Signed: [Signature]  
Well Plugging Supervisor