

DISTRICT CONSERVATION AGENT'S REPORT

15-039-00502-00-00

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 145-26

LOCATION SW NE SE

SEC. 28 TWP. 2 RGE. 28

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease Beck

Operator Stickelman & Betts Address Box 33 Oberlin, Kans

Field _____ County Decatur

Total Depth 3745 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 162' circulated with cement - 5 1/2" at 3745' with 125
sax cement behind - P.B. to 3680' perforated at 3660'.

Filled with sand to 3650', set 4 sax cement with dump bailer,
pulled 3200' 5 1/2" - Gunned bits, circulated hole with heavy mud,
pumped cementing plug to 205', followed by 70 sax cement.

Mudding and Cementing by Globe Cementing Co.

District Conservation Agent

Date 3 15-57

PLUGGING
FILE SEC 28 T 2 R 28w
BOOK PAGE 145 L E 26

COMMISSION
MAR 20 1957
CONSERVATION DIVISION
Wichita, Kansas
3-20-57