

15-147-00010-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Phillips County. Sec. 19 Twp. 2 Rge. 19 (E) W (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. SW SW SW

Lease Owner. Mazda Oil Corporation

Lease Name. Mazda #1 Brands Estate Well No. 1

Office Address. Box 1797, Tulsa 1, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole). Dry hole

Date well completed. July 2, 1944

Application for plugging filed. July 2 1944

Application for plugging approved. July 2 1944

Plugging commenced. July 2 1944

Plugging completed. July 3 1944

Reason for abandonment of well or producing formation. No commercial oil showings

If a producing well is abandoned, date of last production. 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. Eldon Petty

Producing formation. Lan. K. C. Depth to top. 3491' Bottom. 3700' Total Depth of Well. 4121' Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	263'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4121' to 263' - Heavy Mud
263' to 216' - solid plug cemented with 15 sx cement
216' to 30' - Mud
30' to surface - cement - 10 sx



07-07-1944

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Thos. H. Allan
Address. 921 Union National Bank Bldg, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Thos. H. Allan (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thos. H. Allan

921 Union Natl. Bank Bldg., Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of July, 1944.

La Ueda Witt Notary Public.

My commission expires May 12, 1948

15-147-00010-00-00

Casing Record

Phillips County, Kansas

8-5/8" @ 263'

Mazda #1 Brands Estate
SW SW SW Sec. 19, T. 2 S., R. 19W
Commenced: 6/16/44 Completed: 7/2/44
Contractor : Thos. H. Allan
I. P. Dry & Abandoned
Elevation: 2242'

- 0 - 135 soil & sand
- 170 yellow chalk & shale
- 263 Chalky shale
- 263 cemented 8-5/8" casing
- 600 shale & chalk
- 1000 Blue shale
- 1600 Dakota sand & shale
- 1872 Red shale
- 1900 White Anhydrite
- 2380 Red shale
- 2420 sand
- 2870 Lime and shale
- 3154 shale
- 3248 lime & shale
- 3350 Topeka Lime and shale
- 3380 Very soft sandy zone
- 3491 Lime & shale
- 3500 Lansing Lime
- 3725 Kansas City lime with shale breaks
- 3740 Marmaton red sand
- 3850 Shale
- 4110 Dolomite (Arbuckle) soft & hard
- 4121 Granite wash
- 4121 total depth

Formation tops:

- 600 Base Ft. Hays
- 1872 top Anhydrite
- 3248 top Topeka
- 3491 top Lansing
- 3850 top Arbuckle
- 4110 top Granite Wash

I certify that the above is a true and correct copy of the well log on the above test.

Thos. H. Allan

PLUGGING
 FILE NO 19 2-319-4
 BOOK PAGE 123 LINE 21

07-07-1947
1944