

15-147-00654-00-00.

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Phillips County, Sec. 14 Twp. 2 Rge. (E) 19 (W)

Location as "NE/CNW 1/4 SW 1/4" or footage from lines NE NE NE

Lease Owner Howard D. Fink

Lease Name Katherine Weinman Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 23 19 49

Application for plugging filed August 23 19 49

Application for plugging approved August 23 19 49

Plugging commenced August 23 19 49

Plugging completed August 23 19 49

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Stough, Great Bend, Kansas.

Producing formation Depth to top Bottom Total Depth of Well 3450 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	185	none
				Cemented in well from bottom to top as surface casing.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy mud from 3450 feet to 185 feet.  
Plugged with wood plug at 185 feet.  
15 sacks 15 sacks of cement put in at 185 feet.  
Hole filled with heavy mud to 30 feet.  
Plugged with wood plug at 30 feet.  
10 sacks cement to top of hole.

RECEIVED  
08-30-1949  
AUG 30 1949  
STATE CORPORATION COMMISSION  
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to O. G. Stearns,  
Address Russell, Kansas.

STATE OF Kansas, COUNTY OF Russell, ss.

O. G. Stearns (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *O. G. Stearns*  
Russell, Kansas.

SUBSCRIBED AND SWORN to before me this 23rd day of August, 19 49

My commission expires August 17, 1950

*B. F. Keenan*  
Notary Public.

PLUGGING  
FILE SEC 14 T 2 R 19W  
BOOK PAGE 111 LINE 21

15-147-00654-00-00

WEINMAN #1

Location: NE NE/4 NE/4, Sec. 14-T2S-R19W  
Elevation: 2213 Gr., 2216 D. F.

Totco

Howard D. Fink  
Contractor: Stearns Petroleum Incorporated  
Commenced: August 10, 1949  
Completed: August 23, 1949

10 min.	137'
25 min.	560'
40 min.	960'
40 min.	1495'
30 min.	2120'
0°	2495'
10 min.	3155'

Casing Record

8 5/8" casing 185' cemented with 110 sacks

WELL LOG

	<u>FROM</u>	<u>TO</u>
Surface	0	8
Clay	8	80
Sand	80	100
Shale	100	185
Blue shale and sand	185	1495
Red bed	1495	1930
Red shale and shells	1930	2195
Shale and soft lime	2195	2375
Shale and lime	2375	2820
Shale	2820	2945
Shale and shells	2945	3126
Top of Topeka lime		3126
Lime	3126	3345
Top of Kansas City		3345
Lime	3345	3450
		3450 T. D.

STATE OF KANSAS )  
( SS  
County of Russell )

I hereby certify that the above information is true and correct to the best of my knowledge.

**RECEIVED**

Conservation Div.  
AUG 30 1949 8-30-49  
STATE CORPORATION COMMISSION

SUBSCRIBED and sworn to before me this 2nd day of August 1949

B. F. Hervey  
Notary Public

My Commission Expires: August 17, 1950

**PLUGGING**  
FILE SEC 14 T 2 R 1949  
BOOK PAGE 111 LINE 21