

WELL PLUGGING RECORD

K.A.R.-82-3-117

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

TYPE OR PRINT
NOTICE: Fill out Completely
and return to coms. div.
office within 30 days.

API NUMBER 15-159-21,429 -00-00
LEASE NAME Renollet B
WELL NUMBER 5
1980 ft. from ^N Section Line
1320 ft. from ^W Section Line

SEC. 5 TWP. 21 RGE. 6 (E) of (W)
COUNTY Rice

LEASE OPERATOR F.G. Holl Company, LLC
ADDEESS 9431 E. Central, Suite 100, Wichita, KS 67206-2543
PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056
Character of well oil

Date Well Completed 1/1982 kcc
Plugging Commenced 6/25/03 BEM
Plugging Completed 6/27/03 7/13/04

(Oil, Gas, D&A, SWD, input, Water Supply Well)¹³
The plugging proposal was approved on 6/25/03 kcc (date)
by Doug Louis BEM 7/13/04 (XCC District Agent's Name).

Is ACO-1 filed? yes if not, Is well log attached? not available to us

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3545

Show depth and thickness of all water, oil and gas formations
OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	210	none
				5 1/2	3544	2209

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set

Sand at 3387, bail 5 sacks cement. Rip at 2410, 2209, work free. Pull to 1000, pump 35 sacks cement. Pull to 600, pump 35 sacks cement. Pull to 290, circulate cement to surface w/105 sacks. Pull rest of pipe

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925
Address 401 West Main, Lyons, KS. 67554
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company, LLC
STATE OF Kansas COUNTY OF Sedgwick, ss.
Loveness Mpanje (Employee of Operator) or (Operator) of


RECEIVED
JUL 08 2004
KCC WICHITA

above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.

(Signature) _____
(Address) 9431 E. Central, St. 100, Wichita
Kansas, 67206

SUBSCRIBED AND SWORN TO before me 7th day of July, 2004, 20
Betty B. Herring Betty B. Herring
Notary Public

My commission Expires: 04/30/2006



Form CP-4
Revised 05-88