

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: MICA Energy Corp.
Address: P.O. Box 20707, Oklahoma City, OK. 73156
Phone: (405) 942-4552 Operator License #: 32047
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 5-24-04 2/19/04 7/13/04 (Date)
by: Richard Lacey (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Simpson Sh. Depth to Top: 4530 Bottom: 4538 1/2 T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - Spud 1146 151-10072-00-00
Lease Name: KERR
Well Number: 3
Spot Location (QQQQ): NE SW SW SW4 - 150E NW NW
990 Feet from North / South Section Line
1000 Feet from East / West Section Line
Sec. 27 Twp. 29S S. R. 14 East West
County: Pratt
Date Well Completed: 25
Plugging Commenced: 5-24-04 KCC
Plugging Completed: 5-26-04 7/13/04

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface Conductor & Production) | | | | |
|---------------------------|---------|--|----|-------|--------|------------|
| Formation | Content | From | To | Size | Put In | Pulled Out |
| | | | | 8 5/8 | 752 | |
| | | | | 5 1/2 | 4530 | 2520 |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Bridge plug at 4500', bailed 2 sacks of Portland, ripped to 2600', worked pipe no gain, ripped to 2520', worked pipe free, pulled to 800', pumped 50 sacks, pulled to 400', pumped 40 sacks, pulled to 40', pumped 10 sacks, circulated to surface.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
Address: 401 West Main, Lyons, KS 67554
Name of Party Responsible for Plugging Fees: MICA Energy Corp.
State of Oklahoma County, Oklahoma, ss.

RECEIVED
JUL 08 2004
KCC WICHITA

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Clyde D. Sowers
(Address) P.O. Box 20707, Okla. City, OK 73156

SUBSCRIBED and SWORN TO before me this 6th day of July, 2004
David K. Denny My Commission Expires: Oct. 2, 2005
Notary Public