

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

TYPE OR PRINT  
NOTICE: Fill out Completely  
and return to coms. div.  
office within 30 days.

API NUMBER 15-047-20-431-00-00  
LEASE NAME Carpenter #  
WELL NUMBER 1  
990  
1650 2310 <sup>KCC</sup> ft. from S Section Line  
<sub>7/13/04</sub> ft. from E Section Line  
SEC. 5 TWP. 24 RGE. 17 (E) of (W)  
COUNTY Edwards

LEASE OPERATOR F.G. Holl Company, LLC  
ADDEESS 9431 E. Central, Suite 100, Wichita, KS 67206  
PHONE # (316 ) 684-84811 OPERATORS LICENSE NO. 5056  
Character of well oil

Date Well Completed 10/02/1978  
Plugging Commenced 1/28/04 <sup>KCC</sup> <sub>7-13-04</sub>  
Plugging Completed 1/30/04

(Oil, Gas, D&A, SWD, input, Water Supply Well)  
The plugging proposal was approved on 7/28/04 12/5/04 <sup>KCC</sup> <sub>7/13/04</sub> (date)  
by Steve Durant (XCC District Agent's Name)

Is ACO-1 filed? yes if not, Is well log attached? not available to us

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4490  
Show depth and thickness of all water, oil and gas formations

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	261	none
				4 1/2	4488	2462

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set

Sand at 4287, bail 4 sks cement. Rip pipe at 2462, work free, pull to 1250 and pump 15 gel and 50 cem. Pull to 600, pump 40 water, no circulation. Pump 50 gel and 1000 hulls, then 50 cem. Pull to 275, pump 50 cem, pull to 40' and pump 10 cem.

RECEIVED

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925 JUL 08 2004  
Address 401 West Main, Lyons, KS 67554

KCC WICHITA

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company, LLC

STATE OF Kansas COUNTY OF Sedgwick, ss.


Loveness Mpanje (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.

(Signature) Loveness Mpanje  
(Address) 9431 E. Central, St. 100, Wichita KS. 67206

SUBSCRIBED AND SWORN TO before me 7th day of July, 2004

Betty B. Herring Betty B. Herring  
Notary Public

My commission Expires: 04/30/2006



Form CP-4 Revised 05-88

BH