

WELL PLUGGING RECORD

K.A.R.-82-3-117

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

TYPE OR PRINT  
NOTICE: Fill out Completely  
and return to coms. div.  
office within 30 days.

API NUMBER 15-159-21,514 -00-00  
LEASE NAME Mitchell  
WELL NUMBER 2 1 A <sup>KCC</sup> <sup>BEM</sup> <sup>7/13/04</sup>  
1320 ft. from <sup>N</sup> Section Line  
990 ft. from <sup>E</sup> Section Line  
SEC. 4 TWP. 21 RGE. 6 (E) or (W)  
COUNTY Rice  
Date Well Completed 11/17/1982  
Plugging Commenced 7/2/03 <sup>KCC</sup> <sup>BEM</sup> <sup>7/13/04</sup>  
Plugging Completed 7/3/03

LEASE OPERATOR F.G. Holl Company, LLC  
ADDRESS 9431 E. Central, Suite 100, Wichita, KS 67206-2543  
PHONE # (316 ) 684-8481 OPERATORS LICENSE NO. 5056  
Character of well oil

(Oil, Gas, D&A, SWD, input, Water Supply Well)  
The plugging proposal was approved on 7/2/03 <sup>6/13/03</sup> <sup>KCC</sup> <sup>BEM</sup> <sup>7/13/04</sup> (date)  
by Doug Louis (XCC District Agent's Name)

Is ACO-1 filed? yes if not, Is well log attached? not available to us

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3300

Show depth and thickness of all water, oil and gas formations

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	212	none
				4 1/2	3299	2240

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set

Sand at 3082, bail 4 sacks cement. Rip pipe at 2640, 2460, 2240, work free. Pull to 1000, pump 35 sacks cement. Pull to 600, pump 35 sacks cement. Pull to 290, pump 70 sacks cement. Circulate to surface and pull rest of pipe.

RECEIVED

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925 JUL 08 2004  
Address 401 West Main, Lyons, KS 67554 KCC WICHITA

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company, LLC

STATE OF KS. COUNTY OF Sedgwick, ss.

Loveness Mpanje (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.

(Signature) Loveness Mpanje  
(Address) 9431 E. Central, St. 100, Wichita  
KS. 67206

SUBSCRIBED AND SWORN TO before me 7th day of July, 2004, 20

Betty B. Herring Betty B. Herring  
Notary Public

My commission Expires: 04/30/2006

Form CP-4  
Revised 05-88

