



15-039-19027-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 1965

6-1-65

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Owen Bailey of Santa Fe Pipe & Supply has this

date requested permission to plug the following described well:

Union Texas Petr.

Mr. Bailey guarantees payment of the plugging fee.

Operator's full Name: Union Texas Petroleum Corporation,

Complete Address: Drawer "D", Great Bend, Kansas.

Lease Name: Rehm Well No. 1

Location: NE-NE-NW Sec. 33 Twp. 2 Rge. (E) (W) 28

County Decatur Total Depth 3730 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bailey was instructed to plug the well as follows:

197' -- 8 5/8" Surface pipe, cement circulated with 175 Sx.
3723' -- 4 1/2" Production casing cemented with 135 Sx. Top per-
forations @ 3547'.

Sand well back to 3530' and set 3 Sx. cement with dump bailer.
Pull 4 1/2" to 600' and circulate heavy gel mud. Pull 4 1/2" to 540'
and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2" to 210' and dis-
place 20 Sx. cement thru 4 1/2". Pull 4 1/2", set rock bridge @ 35'
and 10 Sx. cement to bottom of cellar.

Very truly yours,

H. L. Deibel
Conservation Division Agent