

4-032345

1-13

15-039-20154-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-

W2 NW SW /4 SEC. 33, 02, 28 W
1980 feet from S section line
4950 feet from E section line

Operator license# 100
Operator: Kansas Corporation Commission
State of Kansas Fee Fund
Address: 2301 E. 13th Street
Hays, Kansas 67601
Control #990032-009

Lease: Paddock Unit Well # 9
County: Decatur
Well total depth 3680 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 318 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Swift Services, Inc. License# 32382

Address: Ness City, Kansas 67560

Company to plug at: Hour: A.M. Day: 13 Month: January Year: 1999

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: Order 220 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 9:00 A.M., Day: 13 Month: January, Year: 1999

Actual plugging report: 8 5/8" set at 318' w/300 sxs cwc. 4 1/2" set at 3679' w/125 sxs. Prod. Perfs 3643' - 3644'. Exempt area for Alt. II. Squeezed 4 1/2" w/170 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 600#. S.I.P. 200#. Squeezed 8 5/8" w/ 50 sxs cement blend. Max. P.S.I. 150#. Plug complete.

Topped off 4 1/2" on January 15, 1999 with 30 sxs cement blend.

RECEIVED
STATE CORPORATION COMMISSION

FEB 01 1999 2-1-99

Remarks:
Condition of casing (in hole): GOOD BAD Any plug: YES NO
Bottom plug (in place): YES , CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

100