

4-032351

1-14

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-039-20150-00-00  
150' S. of  
SE SE /4 SEC. 29, 02, 28 W  
510 feet from S section line  
660 feet from E section line

Operator license# 100 101  
Operator: Kansas Corporation Commission  
State of Kansas Fee Fund  
Address: 2301 E. 13<sup>th</sup> Street  
Hays, Kansas 67601  
Control #990032-001

Lease: Paddock Unit Well # 1  
County: Decatur  
Well total depth 3625 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 259 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Swift Services, Inc. License# 32382

Address: Ness City, Kansas 67560

Company to plug at: Hour: P.M. Day: 14 Month: January Year: 1999

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: Order 220 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All  ], Part [  ], None [  ]

Completed: Hour: 2:45 P.M., Day: 14 Month: January, Year: 1999

Actual plugging report: 8 5/8" set at 259' w/225 sxs cwc. 4 1/2" set at 3624' w/125 sxs. Prod. Perfs 3563' - 3564'. Exempt area for Alt. II. Squeezed 4 1/2" w/225 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 100#. S.I.P. 0#. Squeezed 8 5/8" w/ 50 sxs cement blend. Plug complete.

Topped off 4 1/2" on January 15, 1999 with 70 sxs cement blend.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 01 1999

Remarks:     

Condition of casing(in hole): GOOD      BAD      Anhy. plug: YES X NO     

Bottom plug(in place): YES     , CALC     , NO      Dakota plug: YES X, NO     

Plugged through TUBING     , CASING     . Elevation:      GL

I did  / did not  observe the plugging.

Carl Goodrow  
(agent)

100