

4-032349

1-13

API Number: 15-039-00167-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SE SE SW /4 SEC. 28, 02, 28 W
330 feet from S section line
2970 feet from E section line

Operator license# ~~100~~ 101
Operator: Kansas Corporation Commission
State of Kansas Fee Fund
Address: 2301 E. 13th Street
Hays, Kansas 67601
Control #990032-002

Lease: Paddock Unit Well # 2
County: Decatur
Well total depth 3717 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 217 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Swift Services, Inc. License# 32382
Address: Ness City, Kansas 67560

Company to plug at: Hour: P.M. Day: 13 Month: January Year: 1999

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: Order 265 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All , Part , None

Completed: Hour: 12:30 P.M., Day: 13 Month: January, Year: 1999

Actual plugging report: 8 5/8" set at 217' w/150 sxs cwc. 5 1/2" set at 3716' w/150 sxs.
Prod. Perfs 3591' - 3595'. D.V. Tool set at 1968' w/600 sxs cwc. Squeezed 5 1/2" w/265 sxs
cement blend with 500# hulls mixed in to Max. P.S.I. 500#. S.I.P. 0#. Cement at surface in
braden head. Plug complete.
Topped off 5 1/2" on January 15, 1999 w/30 sxs cement blend.

RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS

FEB 01 1999 8-1-99

Remarks: Condition of casing(in hole): GOOD BAD Any plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did / did not observe the plugging.

Carl Goodrow
(agent)

10.