

4-032348

1-14

15-039-20116-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-

SW NW /4 SEC. 33, 02, 28 W  
3300 feet from S section line  
4620 feet from E section line

Operator license# 100/101  
Operator: Kansas Corporation Commission  
State of Kansas Fee Fund  
Address: 2301 E. 13<sup>th</sup> Street  
Hays, Kansas 67601  
Control #990032-006

Lease: Paddock Unit Well # 6  
County: Decatur  
Well total depth 3615 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 284 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Swift Services, Inc. License# 32382

Address: Ness City, Kansas 67560

Company to plug at: Hour: A.M. Day: 14 Month: January Year: 1999

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: Order 220 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [ X ], Part [      ], None [      ]

Completed: Hour: 1:30 P.M., Day: 14 Month: January, Year: 1999

Actual plugging report: 8 5/8" set at 284' w/200 sxs cwc. 4 1/2" set at 3614' w/125 sxs. Prod. Perfs 3577' - 3588'. Exempt area for Alt. II. Squeezed 4 1/2" w/170 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 750#. S.I.P. 200#. Squeezed 8 5/8" w/ 50 sxs cement blend. Max. P.S.I. 300#. S.I.P. 100#. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 01 1999

2-1-99

Remarks:       
Condition of casing(in hole): GOOD      BAD      Any plug: YES X NO       
Bottom plug(in place): YES     , CALC     , NO      Dakota plug: YES X, NO       
Plugged through TUBING     , CASING     . Elevation:      GL

I did [ X ] / did not [      ] observe the plugging.

Carl Goodrow  
(agent)

100