

4-032343

15-039-20059-00-00

1-14-99

API Number: 15-

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SW SE /4 SEC. 32, 02, 28 W
660 feet from S section line
1980 feet from E section line

Operator license# 100/101
Operator: Kansas Corporation Commission
State of Kansas Fee Fund
Address: 2301 E. 13th Street
Hays, Kansas 67601
Control #990032-011

Lease: Paddock Unit Well # 11
County: Decatur
Well total depth 3779 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 250 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Swift Services, Inc. License# 32382

Address: Ness City, Kansas 67560

Company to plug at: Hour: A.M. Day: 14 Month: January Year: 1999

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: Order 220 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part , None

Completed: Hour: 10:45 A.M., Day: 14 Month: January, Year: 1999

Actual plugging report: 8 5/8" set at 250' w/200 sxs cwc. 4 1/2" set at 3739' w/125 sxs. Prod. Perfs 3591' - 3595'. Exempt area for Alt. II. Squeezed 4 1/2" w/170 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 600#. S.I.P. 200#. Squeezed 8 5/8" w/ 50 sxs cement blend. Max. P.S.I. 600#. S.I.P. 200#. Plug complete. Topped off 4 1/2" on January 15, 1999 with 30 sxs cement blend.

RECEIVED
STATE CORPORATION COMMISSION

FEB 01 1999
2-1-99

Remarks:
Condition of casing(in hole): GOOD BAD Any plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did / did not observe the plugging.

Carl Goodrow
(agent)

170