

4-032303

4-24

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- 039-207170000

SW SW NE /4 SEC. 30, 02, 28 W
2970 feet from S section line
2310 feet from E section line

Operator license# 4273

Lease: Votapka Well # 1-30

Operator: H&R Exploration & Production

County: Decatur 134.88

Address: P.O. Box 101
1113 10th Avenue
Sidney, Nebraska 69162-0101

Well total depth 4150 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 252 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Northwest Well Service License# 31664

Address: Hill City, Kansas 67642

Company to plug at: Hour: A.M. Day: 24 Month: April Year: 1998

Plugging proposal received from: Randy

Company: Northwest Well Service Phone: -

Were: Order 225 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [], Part [X], None []

Completed: Hour: 9:45 A.M., Day: 24 Month: April, Year: 1998

Actual plugging report: 8 5/8" set at 252' w/200 sxs. 5 1/2" set at 4162' w/150 sxs.
Prod.perfs 3761'- 3770'; 3728' - 3740'. PBD 4084'. Set pertinent plug at 3678' with 5 sxs
common cement on plug with bailer. Critical area control shots at 2800' - 1650' and
recovered 1250' of casing. Squeezed 8 5/8" with 200 sxs cement blend with 500# hulls mixed
into Max. P.S.I. 500#. Held. Plug complete.

Remarks: Exempt area for top stage.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: GL

I did [] / did not [X] observe the plugging.

Carl Goodrow
(agent)

INVOICED

10

CONSERVATION DIVISION
Wichita, Kansas

Form CP-2/3

DATE 5-12-98

INV. NO. 50544

5-11-98

4-24

SEP 18 1998