

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-039-2070600-00

BW, Sec. 29, T 2 S, R 28 W/E

1320 feet from ~~N/S~~ section line

1320 feet from ~~W/E~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8684

Lease Name Frickey Well # 2

Operator: Huston Hydrolance
Name &
Address Bx 2723
Victoria Texas

County Decatur

Well Total Depth 3800 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 248

123.50

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Stoepelwerth Drig License Number 8301

Address 1111 E. H St McCook Nebr.

Company to plug at: Hour: PM Day: 28 Month: 10 Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Jack Lowry

(company name) Stoepelwerth Drig (phone) 308 345-1766

were: order 185 sx cem. 50/50 pormix 6% gel 3% c.c.

1 sx hulls - 1 sx Flow seal - 1, 8 5/8 plug.

Heavy mud between all plugs.

Pump. cem. down drill pipe.

Elev. 2542 Anhydrite 2232-66 Arbuckle. No-

Dakota 1350

1192 = 1500

Signed Dale F. Balthazor
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:45 AM Day: 29 Month: 10 Year: 19 83

ACTUAL PLUGGING REPORT

25 sx @ 2240

100 sx @ 1500 mixed with 1 sx Flow seal

40 sx @ 300-, 1 sx hulls, push plug to 40'

10 sx @ 40

10 sx in Rat hole.

Remarks: _____

Cementing w/ Halliburton

I hereby certify that the above plugging instructions were given as herein stated and that I (did did not) observe this plugging.

INVOICED

Signed Dale F. Balthazor
(TECHNICIAN)

DATE _____
INV. NO. 7035-W

RECEIVED
STATE CORPORATION COMMISSION

NOV 10 1983

CONSERVATION DIVISION
Wichita, Kansas

11-10-83

FORM CP-2/3
27 Rev. 9-82