

4-032352

15-039-20109-00-~~XX~~⁰³

1-13

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-
150' E. of
SE SW /4 SEC. 32, 02, 28 W
660 feet from S section line
3150 feet from E section line

Operator license# 100 ¹⁰¹
Operator: Kansas Corporation Commission
State of Kansas Fee Fund
Address: 2301 E. 13th Street
Hays, Kansas 67601
Control #990032-013

Lease: Paddock Unit Well # B-1
County: Decatur
Well total depth 2255 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 249 feet

Aband. oil well___, Gas well___, Input well___, SWD___, D & A___ WSW X

Plugging contractor: Swift Services, Inc. License# 32382

Address: Ness City, Kansas 67560

Company to plug at: Hour: P.M. Day: 13 Month: January Year: 1999

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: Order 125 sxs 60/40 pozmix - 10% gel - 200# hulls.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 3:30 P.M., Day: 13 Month: January, Year: 1999

Actual plugging report: 8 5/8" set at 249' w/175 sxs. 4 1/2" set at 2255' w/300 sxs.
Prod. Perfs 1524' - 1536'. TOC 800'. PBTD 2188'. CIBP's 1985' - 1774' - 1589'.
Squeezed 4 1/2" w/125 sxs cement blend with 200# hulls mixed in to Max. P.S.I. 300#. S.I.P.
75#. Backside circulated to surface. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

1-23 01 1999
2-1-99

Remarks:
Condition of casing(in hole): GOOD___ BAD___ Anhy. plug: YES___ NO___
Bottom plug(in place): YES___, CALC___, NO___ Dakota plug: YES X, NO___
Plugged through TUBING___, CASING___ Elevation: _____ GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

100.