

4-032342

E-16,181

15-039-20082-00-01

1-13

API Number: 15-

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

150' W. of
SE SE / 4 SEC. 32, 02, 28 W
660 feet from S section line
810 feet from E section line

Operator license# 100 101
Operator: Kansas Corporation Commission
State of Kansas Fee Fund
Address: 2301 E. 13th Street
Hays, Kansas 67601
Control #990032-012

Lease: Paddock Unit Well # 12

County: Decatur

Well total depth 3760 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 311 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Swift Services, Inc. License# 32382

Address: Ness City, Kansas 67560

Company to plug at: Hour: P.M. Day: 13 Month: January Year: 1999

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: Order 220 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part , None

Completed: Hour: 2:30 P.M., Day: 13 Month: January, Year: 1999

Actual plugging report: 8 5/8" set at 311' w/225 sxs cwc. 4 1/2" set at 3759' w/125 sxs. Prod. Perfs 3601' - 3603'. Exempt area for Alt. II. Squeezed 4 1/2" w/170 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 750#. S.I.P. 300#. Squeezed 8 5/8" w/ 50 sxs cement blend. Max. P.S.I. 200#. S.I.P. 150#. Plug complete.

Topped off 4 1/2" on January 15, 1999 with 30 sxs cement blend.

RECEIVED
STATE CORPORATION COMMISSION

FEB 01 1999
02-01-99
CONSERVATION DIVISION

Remarks:

Condition of casing(in hole): GOOD BAD Any plug with YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: _____ GL

I did / did not observe the plugging.

Carl Goodrow
(agent)

100.