

4-032346

E-16,181

1-13

15-039-20112-00-01

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-
150' SW of
NE SE / 4 SEC. 32, 02, 28 W
1880 feet from S section line
760 feet from E section line

Operator license# 100 101
Operator: Kansas Corporation Commission
State of Kansas Fee Fund
Address: 2301 E. 13th Street
Hays, Kansas 67601
Control #990032-008

Lease: Paddock Unit Well # 8
County: Decatur
Well total depth 3655 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 303 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Swift Services, Inc. License# 32382
Address: Ness City, Kansas 67560

Company to plug at: Hour: P.M. Day: 13 Month: January Year: 1999

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: Order 220 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All , Part , None

Completed: Hour: 1:30 P.M., Day: 13 Month: January, Year: 1999

Actual plugging report: 8 5/8" set at 303' w/285 sxs cwc. 4 1/2" set at 3654' w/125 sxs.
Prod. Perfs 3627' - 3628'. Exempt area for Alt. II. Squeezed 4 1/2" w/180 sxs cement blend
with 500# hulls mixed in to Max. P.S.I. 300#. S.I.P. 0#. Squeezed 8 5/8" w/ 40 sxs cement
blend. Max. P.S.I. 150#. S.I.P. 100#. Plug complete.
Topped off 4 1/2" on January 15, 1999 with 30 sxs cement blend.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did / did not observe the plugging.

Carl Goodrow
(agent)

100.

RECEIVED
STATE CORPORATION COMMISSION
FEB 01 1999
02-01-99
CONSERVATION DIVISION
WICHITA, KANSAS