

4-032341

E-16,181

1-13

15-039-20119-00-01

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-

NW NW /4 SEC. 33, 02, 28 W  
4950 feet from S section line  
4950 feet from E section line

Operator license# 100101  
Operator: Kansas Corporation Commission  
State of Kansas Fee Fund  
Address: 2301 E. 13<sup>th</sup> Street  
Hays, Kansas 67601  
Control #990032-004

Lease: Paddock Unit Well # 4

County: Decatur

Well total depth 3715 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 277 feet

Aband. oil well\_\_\_, Gas well\_\_\_, Input well X, SWD\_\_\_, D & A\_\_\_

Plugging contractor: Swift Services, Inc. License# 32382

Address: Ness City, Kansas 67560

Company to plug at: Hour: A.M. Day: 13 Month: January Year: 1999

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: Order 220 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 11:00 A.M., Day: 13 Month: January, Year: 1999

Actual plugging report: 8 5/8" set at 277' w/200 sxs cwc. 4 1/2" set at 3714' w/125 sxs.  
Prod. Perfs 3559' - 3560'. Exempt area for Alt. II. Squeezed 4 1/2" w/170 sxs cement blend  
with 500# hulls mixed in to Max. P.S.I. 400#. S.I.P. 100#. Squeezed 8 5/8" w/ 50 sxs cement  
blend. Max. P.S.I. 100#. S.I.P. 75#. Plug complete.  
Topped off 4 1/2" on January 15, 1999 with 70 sxs cement blend.

STATE CORPORATION COMMISSION  
JAN 15 1999  
02-01-99

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD \_\_\_\_\_ BAD \_\_\_\_\_ Anhy.plug: YES X NO \_\_\_\_\_  
Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_. Elevation: \_\_\_\_\_ GL

I did [ X ] / did not [ ] observe the plugging.

Carl Goodrow  
(agent)

ND