

4-032344

E-16,181

1-13

15-039-20176-00-01

API Number: 15-

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

W2 NE SW /4 SEC. 33, 02, 28 W  
1980 feet from S section line  
3630 feet from E section line

Operator license# 100 101

Lease: Paddock Unit Well # 10

Operator: Kansas Corporation Commission  
State of Kansas Fee Fund

County: Decatur

Address: 2301 E. 13th Street  
Hays, Kansas 67601  
Control #990032-010

Well total depth 3710 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 308 feet

Aband. oil well, Gas well, Input well X, SWD, D & A

Plugging contractor: Swift Services, Inc. License# 32382

Address: Ness City, Kansas 67560

Company to plug at: Hour: A.M. Day: 13 Month: January Year: 1999

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: Order 220 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 10:00 A.M., Day: 13 Month: January Year: 1999

Actual plugging report: 8 5/8" set at 308' w/250 sxs cwc. 4 1/2" set at 3709' w/125 sxs.  
Prod. Perfs 3627.5' - 3628.5'. Exempt area for Alt. II. Squeezed 4 1/2" w/170 sxs cement  
blend with 500# hulls mixed in to Max. P.S.I. 500#. S.I.P. 100#. Squeezed 8 5/8" w/ 50 sxs  
cement blend. Max. P.S.I. 200#. S.I.P. 200#. Plug complete.  
Topped off 4 1/2" on January 15, 1999 with 30 sxs cement blend.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks:

Condition of casing(in hole): GOOD BAD Any plug: YES Kansas X NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING. Elevation: GL

I did [ X ] / did not [ ] observe the plugging.

Carl Goodrow  
(agent)

170