

3 022583

15.001.01842-0000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20040026

SE,NE,NW 1/4 Sec/Twp/Rge S.20-T.26S.-R.18E.

4437 feet from south section line

3269 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Lease/Well# CAMPBELL NO.6A

Operator License # 101

County ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 800' feet

Name & FEE FUND PLUGGING

Production Pipe: 2" Size Feet 800'

Address

Surface Casing: 8" Size Feet 20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐ D & A ☐

Other well as hereinafter indicated:

Plugging Contractor: K-W WELL SERVICE, INC.

Lic. # 3096

Address: 19450 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 2:00P.M. Day: 6 Month: 1 2004

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT MAY

HAVE BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS

TO PERFORATE THE 2" CASING SEVERAL TIMES AND TO CIRCULATE AS MUCH OF THE

WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All ☒ Part ☐

TECHNICIAN

None ☐

Operations Completed: Hour: 4:00P.M. Day: 1 Month: 6 2004

Actual Plugging Report: THE 2" CASING WAS PERFORATED AT 200' AND AT 500'.

1" PIPE WAS RAN INTO THE 2" CASING TO 500'. CEMENT WAS PUMPED INTO THE 1"

PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE

WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 33 SACKS OF CEMENT

WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.17)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:



TECHNICIAN

RECEIVED
JUN 21 2004
KCC WICHITA

