

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21320-00-00
Spot: S2NENE Sec/Twnshp/Rge: 28-9S-19W
4290 feet from S Section Line, 660 feet from E Section Line
Lease Name: THYFAULT Well #: 1
County: ROOKS Total Vertical Depth: 3587 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 740, LB 30
DALLAS, TX 75205

PROD Size: 5.5 feet: 3579 w/150 sxs cmt
SURF Size: 8.625 feet: 168 w/135 sxs cmt

\$116⁵⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/09/2004 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS, INC. Phone: (785) 483-1676

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
Braden head squeeze with 400 sxs.
Cleaned out to 1250'.
Cedar Hills sand sluffing back in.
Decided to P&A.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/09/2004 10:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Allied pumped 100 sxs 60/40 pozmix - 10% gel neat, followed with 200 sxs 60/40 pozmix - 10% gel with 500# hulls.
Max. P.S.I. 900#. S.I.P. 400#.
Backside 8 5/8" full of cement.

RECEIVED
JUL 13 2004
KCC WICHITA

Remarks: EMERGENCY PLUG ORDERS GIVEN WITH RIG OVER THE HOLE.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE 7-13-04

NO. 2005060052

Form CP-2/3

JUL 09 2004

JOHN B COLLINS
HAYS KS

replacement card

28-09S-19W
C S/2 NENE

site: 3/4 N OF ZURICH KS
cont: DREILING OIL
sec: LAWRENCE F GRAY
date 05/19/81

#1 THYFAULT

city: ROOKS
field: ZURICH TWST WEST

API 15-163-21320

drig comp 05/23/81 card issued 03/03/81 last received 01/19/98

SLV: 2159 KB, 2:54 GL SMP
tops.....depth/datum
SC.....1524 + 635
TOP.....3094 - 935
HEEB.....3296 - 1137
TOR.....3326 - 1167
LANS.....3341 - 1182
BKC.....3554 - 1395
ARB.....3572 - 1420
RTD.....3597 - 1420
NO LOG

IP status
CAL, ARB 3579-3597, 987 25/81
INFO RELEASED 1/19/98 - WAS OIL WELL - TEMP
COMP
CSG: 0-5/8" 168 / 135 SX, 5-1/2" 3579 / 150 SX
NO CORES OR DSTS RPTD
MICT - CO. (ARB OH), A.C.D, SO, POP, OIL WELL
(POTENTIAL NOT RPTD), 8/25/81 - NO OTHER INFO
AVAILABLE

COPYRIGHT 1995
INDEPENDENT OIL & GAS SERVICE, I.F.C.
WICHITA, KANSAS