

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24294-00-00
Spot: W2SENE Sec/Twnshp/Rge: 5-18S-22W
1980 feet from N Section Line, 1100 feet from E Section Line
Lease Name: JANKE Well #: 2-5
County: NESS Total Vertical Depth: 4450 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: PO BOX 2758 221 N MAIN STE 300
WICHITA, KS 67201

SURF Size: 8.625 feet: 226

\$ 144⁶³

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/30/2004 8:00 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: RICH WHEELER Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 820' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 40 SX CMT. 4TH PLUG AT 40-0' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE
Date/Time Plugging Completed: 06/30/2004 10:15 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

Perfs:


1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 820' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 40 SX CMT. 4TH PLUG AT 40-0' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

RECEIVED
JUL 08 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed

Steve Durrant
(TECHNICIAN)

INVOICED
DATE 7-12-04
INV. NO. 2005060046