

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21001-00-00
Spot: SWSW Sec/Twnshp/Rge: 30-29S-32W
660 feet from S Section Line, 4620 feet from E Section Line
Lease Name: ROSENWINKLE Well #: 1
County: HASKELL Total Vertical Depth: 5700 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: PO BOX 8647
WICHITA, KS 67208

PROD Size: 5.5 feet: 5700 WITH 250 SX CMT
SURF Size: 8.625 feet: 1811 WITH 486 SX CMT

\$185²⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/01/2004 1:45 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAAS Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4750' & 5 SX CMT. PLUG AT 1840' WITH 15 SX GEL & 50 SX CMT. PLUG AT 650' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 07/01/2004 3:00 PM

WitnessType: COMPLETE (100%)
KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 4900'. SAND TO 4750' WITH 5 SX CMT ON TOP. 1ST PLUG PULL CASING TO 1850' & SPOT 15 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 650' & SPOT 40 SX CMT. 3RD PLUG PULL TO 40' & SPOT 15 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4842 | 4844 | | |
| 4834 | 4835 | | |
| 4824 | 4826 | | |
| 4816 | 4819 | | |

RECEIVED
JUL 08 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICE. RECOVERED 2070' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
JUL - 2 2004
KCC Dodge City

Signed

(TECHNICIAN)

INVOICE

DATE 7-12-04

INV. NO. 2005060048