

3 022584

15.001-01837-0000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: STATE OF KANSAS Fee FundName & FEE FUND PLUGGING

Address _____

AB oil well _____ Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W WELL SERVICE, INC.

Lic. #

3096 3097Address: 19450 FORD ROAD, CHANUTE, KANSAS 66720Company to plug at: Hour: 9:00A.M. Day: _____ 3 Month: 6 2004Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT MAYHAVE BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TOPERFORATE THE 2" CASING SEVERAL TIMES AND TO CIRCULATE AS MUCH OF THE WELLAS POSSIBLE FULL OF CEMENT,

Plugging Proposal Received by:

CLAYTON P. TITELPlugging attended by Agent: All X Part _____

TECHNICIAN

None _____

Operations Completed: Hour: 11:00A.M. Day: _____ 3 Month: 6 2004Actual Plugging Report: THE 2" CASING WAS PERFORATED AT 200' AND AT 500'.1" PIPE WAS RAN INTO THE 2" CASING TO 500'. CEMENT WAS PUMPED INTO THE 1"PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPEWAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 30 SACKS OFCEMENT WERE PUMPED INTO THIS WELL.Remarks: (GPS SESSION PT. NO.29) THIS WELL WAS UNNUMBERED ON THE LEASE MAP.(If additional description is necessary, use BACK of this form.)I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED

JUN 21 2004

KCC WICHITA