



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian

WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 4 1974
CONSERVATION DIVISION
Wichita, Kansas
11-4-74

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Zenith Drilling Corporation, Inc.,

Complete Address: Suite 600, 200 W. Douglas, Wichita, Kansas.

Lease Name: May Well No. 1

Location: SW-NW Sec. 32 Twp. 2 Rge. (E)(W) 29

County: Decatur Total Depth 3980' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

220'--8 5/8" Surface casing, cement circulated with 175 Sx.
3976'--4 1/2" Production casing cemented on bottom with 275 Sx. Top perfor-
ations from 3738' to 3741'. Top of cement @ 2750' (Temp. Survey).

Sand well back to 3700' and set 4 Sx. cement with dump bailer. Pull 4 1/2"
casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft.
cement, staged.

Very truly yours,

R. L. Nichols
Conservation Division Agent