



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 1968
CONSERVATION DIVISION
Wichita, Kansas
5-6-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Duane Born of Paine Drilling Co. Inc., has this date requested permission to plug the following described well:

Mr. Born guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Wichita Plaza, Wichita, Kansas.

Lease Name: Pollnow Well No. 1

Location: SE-SE-NW Sec. 30 Twp. 2 Rge. (E)(W) 29

County: Decatur Total Depth 4060 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Born was instructed to plug the well as follows:

326'--7" OD Surface casing, cement circulated with 150 Sx. (6 1/2" Hole).
Top of Dakota section @ 1550'.

Circulate hole with heavy mud. Pull DP to 1775' and displace 60 Sx.
cement thru DP. Pull DP to 335' and displace 15 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 5 Sx. cement to
bottom of cellar.

Very truly yours,

Conservation Division Agent