

State of Kansas



15-039-30074-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 25 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

11-25-68

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clark of Southwest Csg. Pulling Co. Inc. has this date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Hydrocarbon Survey,

Complete Address: 612 Union Center Building, Wichita, Kansas.

Lease Name: Shaw Well No. A-1

Location: SW-SW-SW Sec. 29 Twp. 2 Rge. (E)(W) 29

County: Decatur Total Depth 4010 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Clark was instructed to plug the well as follows:

223'--7" OD Surface casing, cement circulated with 100 Sx. (6 1/4" Hole).  
4009'--Production casing cemented on bottom with 100 Sx. No indication of plug back or perforations.

Sand well back to 3960' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 25 sacks gel plus 3 sacks hulls and 100 Sx. cement staged.

Very truly yours,

*A. B. Dehok*  
 Conservation Division Agent