



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUL 9 1963

7-9-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Leo Swords of Muriin Drilling Co., has this

date requested permission to plug the following described well:

W. T. Waggoner Estate.

Mr. Swords guarantees payment of the plugging fee.

Operator's full Name: W. T. Waggoner Estate,

Complete Address: Box #163, Great Bend, Kansas.

Lease Name: Helmkamp Well No. 1

Location: SW-NE Sec. 6 Twp. 2 Rge. (E) (W) 29

County Decatur Total Depth 4444 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Swords was instructed to plug the well as follows:

240' -- 3 5/8" Surface Pipe, Cement circulated.

Circulate hole with neavy mud, set plug @ 600' & 20 Sx cement.

" " 235' with 1/2 Sk nulls
& 20 Sx cement.
 " " 40' with 1/2 Sk nulls
& 10 Sx cement.

Very truly yours,

W. L. Nichol
 Conservation Division Agent