



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 11 1963
 7-11-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Jim Shipley of Graybol Oil Corp. has this

date requested permission to plug the following described well:

Mr. Shipley guarantees payment of the plugging fee.

Operator's full Name: Graybol Oil Corporation

Complete Address: 2200 National Bank of Tulsa Bldg., Tulsa, Okla.

Lease Name: Castle Well No. 1

Location: SE*NE Sec. 3 Twp. 2 Rge. (E) (W) 29

County Decatur Total Depth 4375 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Shipley was instructed to plug the well as follows:

356'--8 5/8" Surface Pipe, cement circulated.

Circulate hole with heavy mud, set plug @ 600' and 20 Sx cement.

"	"	<u>350'</u>	<u>with 1/2 sk hulls &</u>
			<u>20 Sx cement.</u>
"	"	<u>40'</u>	<u>with 1/2 Sk hulls &</u>
			<u>10 Sx cement.</u>

Very truly yours,

W. A. Nichols
 Conservation Division Agent