

State of Kansas



15-039-00202-00-00

FORM - CP-2  
Rev. 9-8-64

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 5 1964  
11-5-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Mike Wasinger of Knight Csg. Pulling Co. has this

date requested permission to plug the following described well:

Burch Explor. Ltd.,

Mr. Wasinger guarantees payment of the plugging fee.

Operator's full Name: Burch Exploration, Limited,

Complete Address: 1011 Union Center, Wichita, Kansas.

Lease Name: Torluemke Well No. 1

Location: CNE-SW Sec. <sup>35</sup>32 Twp. 2 Rge. (E) (W) 29

County Decatur Total Depth 3895 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Wasinger was instructed to plug the well as follows:

300' -- 8 5/8" Surface pipe, cement circulated,  
3895' -- 4 1/2" Production casing cemented. Well Plugged back to  
3825'. Top perforations from 3768' to 3762'.

Sand well back to 3750' and set 5 Sx. cement with dump bailer.  
Pull 4 1/2" to 600' and circulate heavy gel mud. Pull 4 1/2" to  
540' and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2" to 290'  
and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2", set bridge @ 35'  
and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Nichols  
Conservation Division Agent