

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20281-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 4 1974
CONSERVATION DIVISION
Wichita, Kansas
11-4-74

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Zenith Drilling Corporation, Incorporated,

Complete Address Suite 600, 200 West Douglas, Wichita, Kansas.

Lease Name May Well No. 1

Location SW-NW Sec. 32 Twp. 2 Rge. (E) (W) 29

County Decatur Total Depth 3980'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 12:30 PM Day 28 Month 10 Year 1974

The above well was plugged as follows:

220'--8 5/8" Surface casing, cement circulated with 175 Sx.
3976'--4 1/2" Production casing cemented on bottom with 275 Sx. Top perforations from
3738' to 3741'. Top of cement @ 2750' (Temperature Survey).

Sanded well back to 3700' and set 4 Sx. cement with dump bailer. Pulled 4 1/2" casing
(1600') and squeezed well initially with 5 sacks hulls and 14 sacks gel following with
110 Cu. Ft. cement from 1175' to 1150' then 23 sacks gel from 1150' to 230' and
followed with 30 Cu. Ft. cement from 230' to 155' then 3 sacks gel from 155' to 35'
and finally 10 Cu. Ft. cement from 35' to bottom of cellar. Maximum pump-in pressure-
300#. Final shut-in pressure-100#. (Mudding and cementing by Halliburton).

I hereby certify that the above well was plugged as herein stated.

Signed: M. G. Nichols
Well Plugging Supervisor

INVOICED

DATE 11/4/74

INV. NO. 241-W