

AP

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20042-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 1968
CONSERVATION DIVISION
Wichita, Kansas
5-6-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company,

Complete Address: 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name Pollnow Well No. 1

Location SE-SE-NW Sec. 30 Twp. 2 Rge. (E) (W) 29

County Decatur Total Depth 4060

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Paine Drilling Company, Incorporated,

Address: Box "D", Hill City, Kansas. License No.

Operation Completed: Hour 6:30 PM Day 3 Month 5 Year 1968

The Above well was plugged as follows:

326'--7" OD Surface pipe, cement circulated with 150 Sx. (6 1/4" Hole).
Top of Dakota section @ 1550'.

Circulated hole with heavy mud. Pulled DP to 1775' and displaced 60 Sx. cement thru
DP from 1775 to 1450'. Pulled DP to 335' and displaced 15 Sx. cement thru DP from
335 to 260'. Pulled DP, set bridge @ 30' with 1/2 sack hulls and 5 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Daniels
Well Plugging Supervisor

INVOICED
DATE 5/7/68
INV. NO. 7697-W