

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-30074-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

11-25-68  
RECEIVED  
STATE CORPORATION COMMISSION  
NOV 25 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Hydrocarbon Survey,

Complete Address: 612 Union Center Building, Wichita, Kansas.

Lease Name Shaw Well No. A-1

Location SW SW SW Sec. 29 Twp. 2 Rge. 29W (W)

County Decatur Total Depth 4010

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Southwest Casing Pulling Company, Incorporated,

Address: Box #364, Great Bend, Kansas. License No. 9

Operation Completed: Hour 3:15 PM Day 20 Month 11 Year 1968

The Above well was plugged as follows:

223'--7" Od Surface casing, cement circulated with 100 Sx. (6 1/2" Hole).  
4009'--4 1/2" Production casing cemented on bottom with 100 Sx. No indication of plug back or perforations.

Sanded well back to 3960' and set 3 Sx. cement with dump bailer. Shot and pulled 4 1/2" casing and squeezed well with initially 3 sacks hulls plus 8 sacks gel and followed with 70 Sx. cement from 1710' to 1385' then 14 sacks gel from 1385' to 325' and followed with 20 Sx. cement from 325' to 235' then 3 sacks gel from 235' to 30' and finally 7 sacks cement from 30' to bottom of cellar. Maximum pump-in pressure-250#. Final shut-in pressure 100#. (Mudding and cementing operations performed by Allied Cementing).

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 11/26/68

INV. NO. 8877-4