

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
CORPORATION COMMISSION
FEB 20 1970
CONSERVATION DIVISION
Wichita, Kansas
2-20-70

15-039-20141-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Abercrombie Drilling, Incorporated,
 Complete Address 801 Union Center Building, Wichita, Kansas.
 Lease Name Urban Well No. 2
 Location SW-SW Sec. 16 Twp. 2 Rge. (E) (W) 29
 County Decatur Total Depth 3950'
 Abandoned Oil Well Gas Well Input Well SWD Well D & A X
 Other well as hereafter above indicated
 Plugging Contractor Above
 Address License No.
 Operation Completed: Hour 9:30 AM Day 18 Month 2 Year 1970

The above well was plugged as follows:

226'--7 7/8" Surface casing, cement circulated with 100 Sx. (6 3/4" Hole).
Top of Dakota section @ 1400'

Circulated hole with heavy mud. Pulled DP to 1700' and displaced 65 Sx. cement thru
DP from 1700' to 1375'. Pulled DP to 240' and displaced 15 Sx. cement thru DP from
240' to 175'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 2/20/70
INV. NO. 1470-W