

<sup>N</sup>  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-00728-00-00

RECEIVED  
STATE CORPORATION COMMISSION

JUL 9 1963  
7-9-63  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name W. T. Waggoner Estate,

Complete Address: Box #163, Great Bend, Kansas.

Lease Name Helmkamp Well No. 1

Location SW-NE Sec. 6 Twp. 2 Rge. (E) (W)29

County Decatur Total Depth 4444

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Murrin Drilling Co.,

Address: 617 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 12:00AM Day 5 Month 7 Year 1963

The Above well was plugged as follows:

240'--8 5/8" Surface pipe, cement circulated.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx cement  
thru DP. Heavy mud to 235', set plug with 1/2 Sk hulls and displaced 20 Sx.  
cement thru DP: Heavy mud to 40', set plug with 1/2 Sk hulls and 10 Sx cement  
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 7/9/63  
INV. NO. 7378-W

Signed: W. L. Nichols  
Well Plugging Supervisor