



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-00196-00-00

RECEIVED
STATE CORPORATION COMMISSION

JUL 11 1963

7-11-63

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Graybol Oil Corporation,

Complete Address: 2200 National Bank of Tulsa Bldg., Tulsa, Oklahoma.

Lease Name Castle Well No. 1

Location SE-NE Sec. 3 Twp. 2 Rge. (E) (W) 29

County Decatur Total Depth 4375

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Above

Address: _____ License No. _____

Operation Completed: Hour 8:00AM Day 9 Month 7 Year 1963

The Above well was plugged as follows:

356' --S 5/8" Surface pipe, cement circulated.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx cement thru DP. Heavy mud to 350', set plug and 1/4 sack hulls and displaced 20 Sx cement tnru DP. Heavy mud to 40', set plug and 1/2 sk hulls and 10 Sx cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/11/63

INV. NO. 7393-W

Signed: W. L. Nichols
Well Plugging Supervisor