

DISTRICT CONSERVATION AGENT'S REPORT

TO:

15-039-00071-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 151-0
LOCATION CS $\frac{1}{2}$ S $\frac{1}{2}$ SW
SEC. 33 TWP. 2 RGE. 29

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease _____ Nitsch

Operator L. F. Cushenbery Address Oberlin, Kans

Field _____ County Decatur

Total Depth 4228 Feet.

Plugging Contractor J & M Casing Pulling Co

Plugging Contractor's License No. 11

Address _____ Great Bend,

(Describe briefly the manner in which the well was plugged)

8 5/8" at 193' circulated with cement - 5 1/2" at 3900' with
100 sax cement behind - Lane Wells plugs to 3779' - top perforations
at 3709'.
Chat to 3750', set 4 sax cement with dump bailer, pulled 1200'
5 1/2" - mud to 193', set rock and 15 sax cement, mud to 35', set rock
and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 33 T 2 R 29W
BOOK PAGE 131 LINE 6

RECEIVED
DISTRICT CONSERVATION AGENT
NOV 16 1953
11-16-53

Evan Perry
District Conservation Agent
Date 11-13-53