

9

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20130-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 5 1970
CONSERVATION DIVISION
Wichita, Kansas
1-5-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Tilco, et al.

Complete Address 200 Sutton Place, Wichita, Kansas.

Lease Name Torluemke Well No. 1

Location N/2-SW-NE Sec. 35 Twp. 2 Rge. (E) (W) 29

County Decatur Total Depth 3925'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Leben Drilling, Incorporated.

Address Box #186, Great Bend, Kansas. License No.

Operation Completed: Hour 6:30 PM Day 1 Month 1 Year 1970

The above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 1375'.

Circulated hole with heavy mud, Pulled DP to 1600' and displaced 100 Sx. cement thru
DP from 1600' to 1275'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 1-5-70

INV. NO. 1188-W